

15-179-20203-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Sheridan County, Sec. 29 Twp. 8S Rge. 1E 29 (W)

Location as "NE/CNW%SW%" or footage from lines SW NW SW

Lease Owner Okmar Oil Co. & Adair Oil Co.

Lease Name KOSTER Well No. 1

Office Address 1130 Wichita Plaza; Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 30, 19 69

Application for plugging filed (verbally) April 30, 19 69

Application for plugging approved (verbally) April 30, 19 69

Plugging commenced April 30, 19 69

Plugging completed April 30, 19 69

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4170 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @1550' w/60 sx. cement;
Set 2nd plug @ 275' w/20 sx. cement;
Set top plug @ 40' w/10 sx. cement.
Job was completed at 6:30 p.m., 4-30-69

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1969
CONSERVATION DIVISION
Wichita, Kansas

5-7-69

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address (Office) 801 Union Center; Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
A. L. Abercrombie (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Abercrombie
801 Union Center; Wichita, Kansas
(Address)

Subscribed and sworn to before me this 1st day of May, 19 69

My commission expires July 15, 1972
Sue J. Blunck
Sue J. Blunck, Notary Public.



15-179-20203-0000

CONTRACTOR'S WELL LOG

OWNERS: Okmar Oil Company
 Adair Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: KOSTER #1
 LOCATION: SW NW SW, Sec. 29-8S-29W
 Sheridan County, Kansas
 GEOLOGIST: Sherrill Compton
 SPUD DATE: April 22, 1969
 COMPLETION DATE: April 30, 1969

0	30	Clay
30	70	Sand
70	205	Sand & Rock
205	1875	Shale
1875	2142	Shale & Gyp
2142	2257	Sand
2257	2459	Shale
2459	2496	Anhydrite
2496	2865	Shale
2865	3080	Shale w/Lime Stringers
3080	3347	Shale & Lime
3347	3800	Lime & Shale
3800	3915	Lime
3915	3930	Lime & Shale
3930	4170	Lime
	4170	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 7 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 5-7-69

Drilled 253' of 9" surface hole and set 7", 24# csg. @249' w/80 sx. cement.
 Cement circulated. Plug was down at 6:00 p.m., 4-22-69.
 Dry & Abandoned

SAMPLE TOPS	ELEVATION
Top/Anhydrite 2459 (+ 366)	2825 K. B.
Topeka 3727 (- 902)	2823 D. F.
Heebner 3883 (-1058)	2817 G. L.
Toronto 3903 (-1078)	
Lansing 3920 (-1095)	

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)


Jack K. Wharton, Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KOSTER #1, SW NW SW, Section 29-8S-29W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jack K. Wharton
 Jack K. Wharton

Sworn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick, as of this 5th day of May, 1969.

Sue J. Blynck
 Sue J. Blynck, Notary Public



My Commission Expires:
 July 15, 1972