

15-179-2 0292-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sheridan County. Sec. 30 Twp. 8 Rge. 29 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C NE SW
Lease Owner Okmar Oil Company
Lease Name Geerds #1 Well No. _____
Office Address Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/7/77 _____ 19____
Plugging completed 1/13/77 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4160
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>4 1/2"</u>	<u>4159</u>	<u>2011'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pushed wood plug to 3900' and sanded to 3880', ran 3 sacks cement. Loaded
hole with water, shot pipe at 3504', 3011', 2492', 2006', pulled 64 joints.
Plugged well with 3 sacks hulls, 70 sacks cement, 50-50 pos with 6%
gel, 21 sacks gel, released 8-5/8 plug and ran 60 sacks cement with 50-50
pos, 6% gel.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of Jan., 19 77

Margaret Melcher
Notary Public.

My commission expires _____
RECEIVED
STATE CORPORATION COMMISSION

NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks
My Comm. Exp. Feb. 15, 1979

FEB 04 1977

2-4-77

CONSERVATION DIVISION
Wichita, Kansas

15-179-20292-0000

WELL LOG

OKMAR OIL COMPANY
1130 Vickers-KSB&T Bldg.
Wichita, Kansas 67202

#1 GEERDS
C NE SW Sec. 30-8-29W
Sheridan County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.
CASING RECORD: Set 257.52' 8 5/8"
w/200 sacks 60-40 Pozmix

COMMENCED: 10/29/71
COMPLETED: 11/9/71

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand	0	266	2827 Gr.
Shale & Shells	266	1990	2829 D.F.
Shale	1990	2260	2832 K.B.
Shale & Shells	2260	2469	
Anhydrite	2469	2504	
Shale & Shells	2504	2700	
Shale & Lime	2700	3300	
Lime & Shale	3300	3860	
Lime	3860	3879	
Heebner	3879	3882	
Lime	3882	4160	
Total Depth	4160		

FORMATION TOPS

Anhydrite	2469 +	363
Base Anhy.	2504 +	328
Howard	3583 -	751
Topeka	3668 -	836
Heebner	3878 -	1046
Toronto	3902 -	1070
Lansing	3916 -	1084
T. D.	4160 -	1328

RECEIVED
CORPORATION COMMISSION

OCT 04 1976

CONSERVATION DIVISION
Wichita, Kansas

10-4-76

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NE SW of Section 30-8-29W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Manager

Subscribed and sworn before me this 11th day of November, 1971.

Virginia S. Fabian
Virginia S. Fabian, Notary Public

