

15-179-20306-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sheridan County, Sec. 30 Twp. 8S Rge. (E) 29 (W)
Location as "NE/CNW/SW" or footage from lines N/2 N/2 SW
Lease Owner Okmar Oil Company
Lease Name Geerdes Well No. 2
Office Address 1130 Vickers-KSB&T Bldg., Wichita 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 27, 19 72
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced April 27, 19 72
Plugging completed April 27, 19 72
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (W. L. Nichols of Morland)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4110 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	259'	8-5/8"	259'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Heavy Mud from Total Depth to 1475 Feet,
100 sax Cement; Mud to 275 Feet, 30 sax
Cement; Mud to 40 Feet, 1/2 sax Hulls,
Plug Bridged & 10 sax Cement to Base of
Cellar; 5 sax Cement in Rat Hole. Job
Completed @ 3:15 P.M.

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton 53-72
Address Box 296, Hill City, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employee of owner or owner or operator) of the above described

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of May, 19 72



Louise K. Whitted
Notary Public.

November 26, 1974.

18-179-20306-00-00

DRILLERS LOG

GEERDES NO.1

CASING RECORD:	OPERATOR: Okmar Oil Company	DESCRIPTION:
8-5/8" @ 259' w/225 sax cement	CONTRACTOR: Sage Drilling Co.	N/2 N/2 SW Sec. 30-8S-29W Sheridan Co., Kansas
TOTAL DEPTH: 4110'	COMMENCED: April 20, 1972	ELEVATION: 2828KB
	COMPLETED: April 27, 1972	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	260	
Shale	260	2045	
Sand & Shale	2045	2441	
Anhydrite	2441	2505	
Shale & Shells	2505	2795	
Lime & Shale	2795	3015	
Shale & Lime	3015	3300	
Lime & Shale	3300	3870	
Shale & Lime	3870	3957	
Lime	3957	4110	


RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas

D&A 5-3-72

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 1st day of May, 1972.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.