

15-179-20033-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 1 Twp. 8 Rge. 30 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NE-SW

Lease Owner Leo J. Dreiling Oil Company

Lease Name Feldt Well No. 1

Office Address Route 2, Victoria, Kansas 67671

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-8 1967

Application for plugging filed 8-8 1967

Application for plugging approved 8-8 1967

Plugging commenced 8-8 1967

Plugging completed 8-8 1967

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	325'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran 33 stands in @ 2010' where 1st. plug was set using 100 sacks cement. Ran 6 stands in where 2nd. plug was set at 330' using 20 sacks cement. 3rd. plug was set @ 40' using 1/4 sack hulls and 10 sacks cement, filling to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1967
08-11-1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS (Address)

Subscribed and sworn to before me this 10th day of August, 1967

Joseph A. Hess Notary Public.

My commission expires September 19, 1970

15-179-20033-00-00

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Victoria, Kansas	Sec. 1	Twp. 8	Rng. 30
Farm	Feldt No. 1	Location	NE-SW	
Total Depth	4275'	County	Sheridan	
Comm.	8-2-67	Comp.	8-8-67	Elevation: 2916' K.B. 2913' D.F. 2911' G.R.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671	Cement Record	Production: D & A	
	Casing Record 325' 8 5/8"		175 sacks Cement	

Figures Indicate Bottom of Formations

0'	40'	Surface Soil
40'	77'	Clay
77'	110'	Clay
110'	290'	Clay & Sand
290'	325'	Shale
325'	1124'	Shale W/Sand
1124'	1765'	Shale
1765'	1830'	Sand
1830'	1990'	Shale & Sand
1990'	2003'	Sand W/Shale
2003'	2013'	Anhy.
2013'	2495'	Shale & Shells
2495'	2562'	Shale
2562'	2612'	Anhy.
2612'	2840'	Shale
2840'	3065'	Shale & Lime
3065'	3380'	Shale & Lime
3380'	3490'	Shale & Lime
3490'	3595'	Shale & Lime
3595'	3810'	Shale & Lime
3810'	3930'	Lime & Shale
3930'	4000'	Lime
4000'	4065'	Lime
4065'	4125'	Lime
4125'	4235'	Lime
4235'	4275'	Lime
4275'	T.D.	

RECORDED & INDEXED
 AUG 11 1967
 STATE OF KANSAS
 DEPARTMENT OF REVENUE

STATE OF KANSAS)
) ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Feldt #1.

Leo F. Dreiling
 LEO F. DREILING

Subscribed and sworn to before me this 10th day of August 1967.

Joseph A. Hess
 JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970