


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-179-20315-00-00

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Sheridan County, Sec. 26 Twp. 8S Rge. (E) 30 (W)
Location as "NE/CNW&SW" or footage from lines SE SE NE
Lease Owner Okmar Oil Company
Lease Name Howard Well No. 1
Office Address 1130 Vickers-KSB&T Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 26, 1972
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced June 26, 1972
Plugging completed June 26, 1972
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (W. L. Nichols of Morland)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4205 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	266'	8-5/8"	266'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 4205',
110 sax Cement Plug; Heavy Mud to 280',
30 sax Cement Plug; Mud to 40', 1/2 sax
Hulls, Plug Bridged and 10 sax Cement
to Base of Cellar; 2 sax Cement in Rat
Hole. Job Completed @ 11:30 A.M. 6/26.

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1972
06-29-1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor HOWCO
Address Box 339, Hays, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
Clarence Michael of Sage Drilling Co. (employee of owner) or owner or operator of the above described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael
500 Bitting Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of June, 1972

My commission expires November 26, 1974.

Louise K. Whitted - Notary Public.



15-179-20315-00-00

DRILLERS LOG

HOWARD NO. 1

CASING RECORD:	OPERATOR: Okmar Oil Company	DESCRIPTION:
8-5/8" @ 266' w/225 sax cement	CONTRACTOR: Sage Drilling Co.	SE SE NE Sec. 26-8S-30W Sheridan County, Kans.
TOTAL DEPTH: 4205'	COMMENCED: June 19, 1972	ELEVATION: 2861KB
	COMPLETED: June 26, 1972	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Sand	0	270	
Shale	270	1830	
Shale & Sand	1830	2460	
Shale	2460	2495	
Anhydrite	2495	2533	
Shale	2533	2660	
Shale & Lime	2660	3130	
Lime & Shale	3130	3420	
Lime	3420	3660	
Chalky Lime	3660	3900	
Lime	3900	4205	D&A

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 29 1972
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael
Clarence Michael



Subscribed and sworn to before me this 27th day of June, 1972.

Louise K. Whitted
 Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.