

ORIGINAL

Side Two

CONFIDENTIAL

Operator Name: Lotus Operating Company, LLC Lease Name: Morris Herl Well #: 1
 Sec. 3 Twp. 16 S. R. 18 East West County: Rush

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:
 Dual Induction, Neutron/Density
 Microlog

Name	Formation (Top), Depth and Datum	Top	Datum
Anhy	1084	+855	
Heebner	3160	-1221	
Lans	3209	-1270	
BKC	3438	-1449	
Arb	3504	-1565	
RTD	3610	-1671	
LTD	3610	-1671	

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./ Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8	23#	1130	Common	450	3% CC/2% Gel
Production	7 7/8	4 1/2	10.5#	3587	60/40 Poz	225	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	3489-93 - GAUGE GAS - LOW BTU		
	CEBPE 3480		
4	3249-53 & 3232-35	ACID 3500 GAL	
4	2926-30	ACID 500	

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2 3/8	3431'	None	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.		Producing Method			
WAIT ON SURFACE EQUIPMENT		<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Other (Specify)

Production Interval Dually Comp. Commingled

KCC
MAY 11 2006
CONFIDENTIAL

ALLIED CEMENTING CO., INC. 25085

Federal Tax I.D.#

ATTN: P.O. BOX 31
 RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

DATE <u>3-2-06</u>	SEC. <u>3</u>	TWP. <u>16</u>	RANGE <u>18</u>	CALLED OUT	ON LOCATION <u>3:00pm</u>	JOB START <u>10:45pm</u>	JOB FINISH <u>11:45pm</u>
LEASE <u>Morris</u>	WELL # <u>1</u>	LOCATION <u>Hays S. to Co. Line 1 1/2 E</u>		COUNTY <u>Rush</u>	STATE <u>Ks</u>		
OLD OR NEW (Circle one)		Sino					

CONTRACTOR MJB

TYPE OF JOB Production String

HOLE SIZE _____ FD. 3610

CASING SIZE 4" 10lb DEPTH 3587

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT 10'

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 58 Bbl

EQUIPMENT

PUMP TRUCK CEMENTER Steve

409 HELPER Chenn

BULK TRUCK _____

3102 DRIVER Jody

BULK TRUCK _____

_____ DRIVER _____

REMARKS:

15 days Rest Hole

Plug bonded 1500psi. Float Held

Thank You

OWNER _____

CEMENT

AMOUNT ORDERED 250 60/40 26 bbl

750 Salt 500 bbl WFR2

COMMON	<u>150</u>	@	<u>960</u>	<u>1440 00</u>
POZMIX	<u>100</u>	@	<u>520</u>	<u>520 00</u>
GEL	<u>A</u>	@	<u>1500</u>	<u>60 00</u>
CHLORIDE		@		
ASC		@		
<u>Salt</u>	<u>17</u>	@	<u>1730</u>	<u>294 10</u>
<u>WFR-2</u>	<u>500 gals</u>	@	<u>100</u>	<u>500 00</u>
HANDLING	<u>211</u>	@	<u>120</u>	<u>460 70</u>
MILEAGE	<u>7 1/2/sk/mile</u>			<u>750 00</u>
TOTAL				<u>4033 60</u>

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>1450 00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>40</u>	@	<u>500</u> <u>200 00</u>
MANIFOLD		@	
TOTAL <u>1650 00</u>			

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 15 2006

CHARGE TO: Lotus Operating

STREET _____

CITY _____ STATE _____ ZIP _____

CONSERVATION DIVISION
 WICHITA, KS

PLUG & FLOAT EQUIPMENT

<u>1 AFU Insert</u>	@	<u>235 00</u>
<u>5 Gaskets</u>	@	<u>50 00</u> <u>250 00</u>
<u>1 Rubber Plug</u>	@	<u>60 00</u>
TOTAL <u>545 00</u>		

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Art Schenck

PRINTED NAME

PAID
 3/5/06

