


15-065-00434-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 5 Twp. 8 Rge. 25 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines NE NE SE  
Lease Owner Trans Era Petroleum, Inc.  
Lease Name Hulburt Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 19 19 54  
Application for plugging filed June 18 19 54  
Application for plugging approved June 18 19 54  
Plugging commenced June 19 19 54  
Plugging completed June 19 19 54  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4535 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	179'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 175', set bottom plug at 175' with one-half sack of hulls and 15 sacks of cement mixed and poured through drill pipe. Filled hole with heavy mud to 40', set top plug at 40' with one-half sack of hulls and 10 sacks of cement used.


RECEIVED  
STATE CORPORATION COMMISSION  
JUL 3 1954  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Trans Era Petroleum, Inc. 7-3-54  
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Michaelis  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of June, 1954  
My commission expires 1-30-57  
Margie Cooper Notary Public.



PLUGGING  
FILE SEC 5 T 18 R 25  
BOOK PAGE 42 LINE 18

Trans Era Petroleum, Inc.  
Hulburt #1

NE NE SE 5-8-25  
Graham County, Ks.

Total Depth: 4535'  
Comm. 6/4/54  
Comp. 6/19/54

Casing

8 5/8" Set @ 179'

Cement

140 sacks Lone Star

Formation	Depth
Clay-sand-shale	179
Shale-sand	1010
Shale	1675
Sand-red bed	1865
Shale-red bed	2094
Anhydrite	2133
Red bed-shale	2210
Shale	2640
Shale-lime	3688
Lime	4094
Lime-shale	4268
Shale-lime-chert	4320
Chert	4345
Lime	4410
Viola	4464
Lime	4490
Dolomite-Simpson	4515
Arbuckle	4535'

STATE OF KANSAS )  
 STATE OF KANSAS )  
 JUL 7 1954  
 COMMISSIONER )  
 7-3-54

STATE OF KANSAS )  
 ) ss  
 RUSSELL COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

-----  
*Cora Betz*  
 -----

Subscribed and sworn to before me this 30th day of June, 1954.

-----  
*Margie Cooper*  
 -----  
 Notary Public

My commission expires: 1-30-57.



PLUGGING  
 WELL SEC 5 T 8 R 25 W  
 BOX PAGE 42 LINE 18