

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Graham County, Sec. 5 Twp. 8S Rge. 25W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE SW SW

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Davis Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 29, 1957

Application for plugging filed June 29, 1957

Application for plugging approved June 29, 1957

Plugging commenced June 29, 1957

Plugging completed June 29, 1957

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4015 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	6-19-57	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole with heavy mud to 500'  
dumped 25 sacks cement and mud to  
30', dumped 10 sacks cement to bottom  
of cellar. Completed 11:30 PM 6-29-57

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1957  
CONSERVATION DIVISION  
Wichita, Kansas

7-12-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address 903 Union National Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) By: Raymond L. Bacon V-P

903 Union National Building, Wichita 2, Kansas (Address)

Subscribed and sworn to before me this 11th day of July, 19 57

December 19, 1960

Louetta M. Duncan  
Louetta M. Duncan

Notary Public.



PLUGGING  
FILE SEC 5 T 8 R 25W  
BOOK PAGE 24 LINE 29

15-065-02255-00.00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.  
903 Union National Building  
Wichita 2, Kansas

Davis No. 1  
SE SW SW Sec. 5-8S-25W  
Graham County, Kansas

Total Depth: 4015'

Elevation: 2511' R.B.  
Production: D & A

Commenced: 6-20-57 Completed: 6-29-57

Contractor: Imperial Oil of Kansas, Inc.  
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 218' with 175 sacks cement.

Figures indicate bottom of formations:

Sand & Clay	140'		<u>TOPS</u>	
Shale & Shells	625'			
Sandy Shale	675'	Anhydrite	2200'	(-311)
Shale	985'	Heebner	3756'	(-1245)
Sand	1240'	Lansing	3794'	(-1283)
Shale	1470'	Total Depth	4015'	(-1504)
Shale, Shells & Sand	1975'			
Red Bed & Shale	2200'			
Anhydrite	2230'			
Shale & Shells	2650'			
Shale & Lime	3085'			
Lime	3315'			
Lime & Shale	3720'			
Lime	4015'			
Total Depth	4015'			

We hereby Certify this to be a correct and accurate log of the above described well as shown on the data drilling reports.



RECEIVED  
JUL 12 1957  
CONSERVATION DIVISION  
Wichita, Kansas

IMPERIAL OIL OF KANSAS, INC.

By: Stanley J. Bowers  
Vice-President

7-12-57

Subscribed and sworn to before me this 10th day of July, 1957.

My Commission Expires:

December 19, 1960

PLUGGING
FILE SEC. 5 1 8 R 25W
BOOK PAGE 24 LINE 29

Luella M. Adams