


13-065-02775-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 5 Twp. 8 Rge. (E) 25(W)
Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner C-G Drilling Company
Lease Name Toll Well No. # 2
Office Address Box 637 Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Abandoned Oil Well
Date well completed November 21 19 57
Application for plugging filed yes 19
Application for plugging approved yes 19
Plugging commenced 9-22-61 19
Plugging completed 9-26-61 19
Reason for abandonment of well or producing formation No longer commercial

If a producing well is abandoned, date of last production September 12 19 61
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation Lans. - K.C. 3788-3999' Depth to top _____ Bottom _____ Total Depth of Well 3935' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4027'	2,986'
				8-5/8"	207.87'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 9-22-61. Plugging completed 9-26-61.

Measured in to total depth: 3935'.

Plugged off bottom: Sanded back from 3935' to 3900' and dumped 5 sacks of cement.

Worked and shot 5 1/2" casing free at 2986'. Built rack and slide. Pulled and layed down casing.

Plugged well: Through 5 1/2": Circulated 40 sacks mud at 500' and pumped 20 sacks cement. Pumped 20 sacks cement at 250'. Capped the well with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1961

CONSERVATION DIVISION
Wichita, Kansas
10-13-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J. O. Forbes


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of October, 19 61

My commission expires December 8th, 1963

Kayann Jenkins
Notary Public.



WELL LOG

OPERATOR C-G Drilling Co. & N. Appleman Co. SEC. 5-8-25W
 WELL NAME Toll #2 LOC. SW SE SW
 TOTAL DEPTH 4030' COUNTY Graham
 Drilling Drilling STATE Kansas
 COMM. November 11, 1957 COMP. November 21, 1957 ELEVATION 2508' K.B.
 RIG NO. 2
 CASING: Left in hole 207.87' 8-5/8" OD Surface PRODUCTION: Plugged
 Casing. & Abandoned
 And 1041' OD Casing. 5-1/2". September 26, 1961

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	700	Shale & Sand		
700	1075	Shale & Shells		
1075	1200	Sand		
1200	1500	Shale & Sand		
1500	2189	Shale & Shells		
2189	2220	Anhydrite		
2220	2665	Shale & Shells	00 - 2500	
2665	3746	Shale & Lime	00 - 2750	DST 3895-3920'
3746	4030	Lime	00 - 3000	DST 3924-3938'
			00 - 3250	DST 3934-3955'
			00 - 3500	DST 3955-3990'
			00 - 3750	

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 13 1961
 CONSERVATION DIVISION
 Wichita, Kansas
 10-13-61

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.
 By G. F. Galloway

G. F. Galloway
 THIS 3rd day of October, 1961.

Vicky Jacobs
 Vicky Jacobs - Notary Public

