


15-065-00713-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 6 Twp. 8 Rge. 25 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner Trans Era Petroleum, Inc.
Lease Name Davis Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6/13/55 19
Application for plugging filed 6/12/55 19
Application for plugging approved 6/12/55 19
Plugging commenced 6/12/55 19
Plugging completed 6/12/55 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4585 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	203	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 200' and set first plug, using 1/2 sack hulls and 15 sacks cement through drill pipe. Filled hole to 40' with heavy mud and set 2nd plug, using 10 sacks of cement. Tied top plug.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Trans Era Petroleum, Inc.
Address Box 633, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
ROBERT B. SNYDER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert B. Snyder

(Address) _____

Subscribed and Sworn to before me this 23rd day of June, 1955
My commission expires 1-30-57
Margie Cooper Notary Public.



PLUGGING
FILED SEC 6 T 8 R 25u
BOOK PAGE 126 LINE 27

624-55
CONSERVATION DIVISION

15-065-00713-00-00

Trans Era Petroleum, Inc.
Davis #1

SW SW SE 6-8-25
Graham County, Kansas

Total Depth: 4585

Comm: 5/26/55
Comp: 6/13/55

Casing:

8 5/8" @ 203

Cement:

150 sacks of Victor

FORMATION	DEPTH
Surface Clay	40
Sand	115
Shale	125
Sand	155
Shale & Shells	213
Shale	680
Sand, Shale & Shells	810
Shale & Shells	1030
lime, Shells & Sand	1100
Shale & Shells	1300
Shale & Sand	1525
Shale & Shells	1695
Red Bed & Shale	1820
Sand	1915
Red Bed & Shale	2180
Anhydrite	2210
Shale & Shells	2670
Shale & Lime	3790
Lime	4030
Lime & Shale	4307
Mississippi	4449
Miss. Viola	4524
Simpson	4531
Arbuckle	4585

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

Robert B. Smyler

Subscribed and sworn to before me this 23rd day of June, 1955.

Margie Cooper
Notary Public

NO. _____ CASE _____ LINE _____

My commission expires: 1-30-57



RECEIVED
OIL & GAS CORPORATION COMMISSION
JUN 24 1955
CONSERVATION DIVISION
Wichita, Kansas

6-24-55

PLUGGING
FILE SEC 6 T 8 R 25W
BOOK PAGE 26 LINE 27