


15-065-02776-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 8 Twp. 8S Rge. 25 (E/W) (W)



Locate well correctly on above Section Plat

Location as "NE/CNWKSWK" or footage from lines SW/NW/NE
Lease Owner C-G Drilling Company
Lease Name Toll Well No. "A" #1
Office Address Box 637, Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 21, 1957
Application for plugging filed Yes
Application for plugging approved Yes
Plugging commenced 1-15 19 59
Plugging completed 1-22 19 59
Reason for abandonment of well or producing formation No longer commercial

If a producing well is abandoned, date of last production December 18, 1958
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fabricius
Producing formation K.C. Lansing Depth to top 3798' Bottom 4010' Total Depth of Well 4020' Feet
Show depth and thickness of all water, oil and gas formations. Produced from 3959-3965'


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	201.97'	None
				5 1/2"	4019'	3,213'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 4020'.
Plugging started 1-15-59. Finished 1-22-59.
Plugged off bottom and sanded to 3950'. Dumped 3 sacks cement.
Shot 5 1/2" casing at 3,213'. ~~Pulled pipe~~ out of hole and plugged well as follows: Plugged with mud to 170'. Set rock bridge and dumped 25 sacks cement. Filled hole with mud. Set rock bridge and mixed 10 sacks cement for cap on well. Well completed.



Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co. 2-3-59
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend Kans.
(Address)



SUBSCRIBED AND SWORN to before me this 27th day of January, 1959
Betty S. Edman
Notary Public.

PLUGGING
FILE SEC. 8 T. 8 R. 25W
BOOK PAGE 13 LINE 1

W E L L L O G

OPERATOR N. Appleman Company SEC. 8-8-25W
 WELL NAME Toll "A" #1 LOC. SW NW NE
 TOTAL DEPTH 4020' RIG NO. 2
 DRILLING COMMENCED October 31, 1957 COUNTY Graham
 DRILLING COMPLETED November 10, 1957 STATE Kansas
 PLUGGED & ABANDONED January 22, 1959 ELEVATION 2514' R.B.
 CASING LEFT IN HOLE: 201.97' (10 jts.) DRY & ABANDONED
 8-5/8" OD Surface Casing.
 806' of 5-1/2" OD Casing (Casing originally set @4019'; 3213' of casing pulled.)

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	965	Shale & Sand		
965	2198	Shale & Sand		
2198	2235	Anhydrite		
2235	2790	Shale & Shell	0° - 2500	
2790	3751	Shale & Lime	0° - 2750	
3751	3836	Lime & Shale	0° - 3000	DST 3924-3951'
3836	4020	Lime	0° - 3250	DST 3947-3966'

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 3 1959
 CONSERVATION DIVISION
 Wichita, Kansas

23-59

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway
 G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 26th day of January, 1959.



My commission expires: May 20, 1959

Vicky Jacobs
 Vicky Jacobs -----Notary Public

PLUGGING
 FILE SEC 8 T 8 R 25W
 BOOK PAGE 13 LINE 1