

15-065-21435-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

FORM CP-4

WELL-PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
200 Colorado Derby Bldg.
202 W. 1st St.
Wichita, KS 67202

Graham County Sec. 8 Twp 8S Rge. 25 E/W
Location as "NE/CNW/SW" or footage from lines
SE SW NW

Lease Owner Beren Corporation
Lease Name Madden-Schmied Well No# 4
Office Address 970 Fourth Financial Center Wichita, Ks
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole


Date Well completed July 22 19 81
Application for plugging filed July 22 19 81
Application for plugging approved July 22 19 81
Plugging commenced 10:30 A.M. July 22 19 81
Plugging completed 11:45 A.M. July 22 19 81
Reason for abandonment of well or producing formation
No Commercial Production

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Tl. Depth of Well _____
Show depth and thickness of all water, oil and gas formations.

locate well correctly
on above
Section Plot



OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface casing	common	0'	323.37'	8 5/8"	323.37'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Plug #1 1100' with 60 sxs
- Plug #2 340' with 30 sxs
- Plug #3 40' with 10 sxs
- 5 sxs in rathole
- Total - 105 sxs 50-50-pos 6% gel

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pioneer Drilling Co, Inc.
308 West Mill Plainville, Ks 67663

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Max S. Houston (employee of owner) ~~or owner or operator~~ of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well is filed and that the same are true and correct. So help me God.

(Signature) Max S Houston
(Address) 970 Fourth Financial Center
Wichita, Kansas 67202

RECEIVED
AUG 28 1981
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 27th day of August, 19 81

My commission expires 11-4-84

Karen J. Berry
Notary Public

15-065-21433-00-00

WELL LOG

OPERATOR: Beren Corporation

WELL NAME: Madden-Schmied #4 LOCATION: SE SW NW 8-8S-25W

COUNTY: Graham STATE: Kansas

WELL COMMENCED: July 14, 1981 WELL COMPLETED: July 22, 1981

ELEVATION: 2481' K.B. TOTAL DEPTH: 4000'

PRODUCTION: D & A RIG NO: #2

CASING - 8 5/8": 8 Jts new 24# set @ 323.37' cemented with 235 sxs common 2% gel 3% cc

5 1/2": P.D. @ 4:00 A.M. did not circ.


ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	100'	sand and shale		
100'	332'	sand and shale	332' - 1/4 degree	
332'	1234'	sand and shale		
1234'	1304'	sand and shale	1304' - 1 3/4 degree	
1304'	1540'	sand and shale		
1540'	2154'	sand and shale		
2154'	2171'	sand and shale		
2171'	2213'	anhydrite		
2213'	2377'	sand and shale	2377' - 3/4 degree	
2377'	2585'	lime and shale		
2585'	2815'	lime and shale		
2815'	3082'	lime and shale		
3082'	3230'	lime and shale		
3230'	3400'	lime and shale		
3400'	3510'	lime and shale		
3510'	3620'	lime and shale		
3620'	3760'	lime and shale		
3760'	3845'	lime and shale	3845' - 0 degree	
3845'	3875'	lime and shale		
3875'	3943'	lime and shale		
3943'	3960'	lime and shale		
3960'	4000'	lime and shale		
4000'	R.T.D.			

STATE OF KANSAS

COUNTY OF _____

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct



PIONEER DRILLING CO., INC.

By Stacy A. Hilgers

SUBSCRIBED AND SWORN TO, BEFORE ME, This 29th day of July, 1981

Judy Smith
NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION
7-30-81
JUL 30 1981
CONSERVATION DIVISION
Wichita, Kansas