


15-065-21633-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 8 TWP. 8S RGE. 25 (W)
 Location as in quarters or footage from lines:
2338' FNL, 2210' FEL SW SW NE



Locate Well
 correctly on above
 Section Platt.

Lease Owner Industrial Gas Services
 Lease Name Toll Well No. 1-8
 Office Address 4501 Wadsworth Blvd., Wheat Ridge, CO 80033
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 5/25/82
 Application for plugging filed Mr. Dennis Hamill gave verbal authorization 3:45 PM 5/25/82
 Plugging commenced 5/25/82
 Plugging completed 5/25/82
 Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Dennis Hamill
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4020
 Show depth and thickness of all water, oil and gas formations. /

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0	261	8 5/8	261 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Well plugged with 150 sx 50/50 Pozmix, 12% gel, 3% CaCl as follows:
 20 sx @ 2212'
 70 sx @ 1250'
 40 sx @ 260'
 10 sx @ 40'
 10 sx in rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations (Job by Halliburton)

STATE OF Colorado COUNTY OF Jefferson, ss.
Robert M. Richardson (employee of ~~owner~~ or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert M. Richardson ENGR. MGR.
 4501 Wadsworth Blvd, Wheat Ridge,
 (Address) Colorado 80033

SUBSCRIBED AND SWORN TO before me this 28TH day of May, 19 82

L. Dine Notary Public.

My Commission expires: Feb. 2, 1986

4501 Wadsworth Blvd
 Wheat Ridge, CO 80033
 RECEIVED
 STATE CORPORATION COMMISSION
 JUN - 1 1982
 CONSERVATION DIVISION
 Wichita, Kansas

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665

15-065-21633-00-00

DRILLERS LOG

OPERATOR: Industrial Gas Services, Inc.
4501 Wadsworth Blvd.
Wheatridge, CO 80033

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Toll WELL: #1-8

LOCATION: SW SW NE
Section 8-8-25W
Graham County, Kansas

Total Depth: 4020'

Elevation:

Commenced: 5-16-82

Completed: 5-25-82

Casing: 8-5/8" @ 261' with 160 sks cement

Status: Dry hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & limestone	40'	Shale	2178'
Sand, shale & limestone	266'	Anhydrite	2213'
Sand & shale	1666'	Shale & lime	3972'
Shale	1770'	Lime (R.T.D.)	4020'
Sand	1946'		

STATE OF KANSAS)

ss:

COUNTY OF RUSSELL)


Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Joe K. Branum

Joe K. Branum

Subscribed and sworn to before me this 26th day of May, 1982.

My Commission Expires: April 29, 1984.



Joyce Ann Ridgley

Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1982
5-28-82
CONSERVATION DIVISION
Wichita, Kansas