

15-065-20985-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Graham SEC. 9 TWP. 8S RGE. 25W E/W  
Location as in quarters or footage from lines:


SE SW NE

Lease Owner J.A. Allison  
 Lease Name Lake Well No. #1  
 Office Address 300 W. Douglas Suite 305 Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 9-28-81  
 Plugging completed 10-2-81  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3915'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	228'	none
				5-1/2"	3912'	3008'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

~~Moved in on location, plugged off bottom with sand to 3750' and set 5 sacks cement.  
Got 13" stretch, shot pipe @3020' and pulled 91 joints of pipe. Plugged well with 3 sacks  
hulls, 28 sacks gel, 8-5/8" plug, 130 sacks 50/50 pos, 6% gel. Plugging completed.~~

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1981

My Commission expires:



Irene Hoover  
Notary Public

STATE CORPORATION COMMISSION  
10-15-81  
OCT 15 1981

CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

15-065-20985-0000

OPERATOR: J. A. Allison  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Lake #1  
 LOCATION: SE SW NE Section 9-8S-25W  
 Graham County, Kansas  
 SPUD DATE: December 23, 1977  
 COMPLETION DATE: January 3, 1978

0	230	Surface soil, sand & shale
230	670	Shale
670	1500	Shale & sand
1500	1898	Shale & lime
1898	2066	Shale
2066	2100	Anhydrite
2100	2320	Shale
2320	2634	Lime & shale
2634	2876	Shale
2876	3218	Lime & shale
3218	3706	Shale & lime
3706	3754	Lime
3754	3763	Shale & lime
3763	3805	Lime
3805	3837	Lime & shale
3837	3875	Lime
3875	3915	Shale & lime
	3915	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION

MAY 15 1981

CONSERVATION DIVISION  
Wichita, Kansas

5-15-81

Spud hole at 3:00 p.m., December 23, 1977. Drilled 230' of 12 1/4" hole. Ran 5 joints of 8-5/8" - 28# surface casing. Set at 228.50'. Cemented with 165 sacks common cement, 2% gel, 3% CaCl. Cement did circulate. Job was complete at 9:30 p.m., December 23, 1977.

T.D. 3915'. Ran 119 joints of 5 1/2" - 14# K-55 casing. Set at 3911.90'. Cemented with 150 sacks 60/40 posmix, 2% gel, 10% salt, followed with 10 bbls. salt flush. Plug at 3884'. Job was complete at 7:45 p.m., January 3, 1978.

STATE OF KANSAS )  
                          ) ss  
COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Lake #1, SE SW NE Section 9-8S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
Jack L. Partridge,  
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 13th day of January, 1978.



Sandra Richman  
Sandra Richman, Notary Public