


STATE OF KANSAS
STATE CORPORATION COMMISSION

13-065-00013-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 13 Twp. 8S Rge. 25 ~~(E)~~ (W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Empire Drilling Company
Lease Name Covalt Well No. 1
Office Address 650 Fourth National Bank Bld., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 6, 1962 19
Application for plugging filed March 6, 1962 19
Application for plugging approved March 6, 1962 19
Plugging commenced March 6, 1962 19
Plugging completed March 6, 1962 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3950 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Shale	0	132	8 5/8"	130'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 540' with 20 sacks cement.
Plug set at 150' with 20 sacks cement.
Plug set at 35' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1962
CONSERVATION DIVISION
Wichita, Kansas

3-13-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld (employee or owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 Fourth Nat'l Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of March, 19 62

My commission expires October 21, 1962.

Lucille H. Harr
Notary Public.



LOG

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Cevalt # 1
 LOCATION: NW NW NE of Section 13-8S-25W, Graham County, Kansas
 COMMENCED: February 26, 1962
 COMPLETED: March 6, 1962
 ELEVATION: 2975 KB
 POTENTIAL: D & A

0	to	132	Surface Shale
132	to	625	Shale
625	to	1300	Shells-Shale with Pyrite
1300	to	1650	Shale-Shells
1650	to	2093	Sand-Shale
2093	to	2125	Anhydrite
2125	to	2310	Shale
2310	to	2690	Shale-Shells
2690	to	3105	Shale-Lime
3105	to	3193	Lime
3193	to	3440	Lime-Shale
3440	to	3485	Shale
3485	to	3650	Shale-Lime
3650	to	3800	Lime
3800	to	3895	Lime-Shale
3895	to	3950	Lime
3950			Rotary Total Depth

RECEIVED
 MARCH 1 1962
 3-13-62

SET: 130' of 8 5/8" casing with 75 sacks cement.

ELECTRIC LOG TOPS:

Heebner	3672	-2197
Terente	3698	-1323
Lansing	3716	-1341
Base Kansas City	3932	-1557
Log Total Depth	3951	

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Cevalt # 1, NW NW NE of Section 13-8S-25W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 12th day of March, 1962.



Lucille H. Marr
 Lucille H. Marr, Notary Public

My commission expires October 21, 1962.