

State of Kansas



15-065-02858-020

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

7/3/67 JUL 3 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sam Bradley of Pipe Pullers, Inc., has this

date requested permission to plug the following described well:
Four Way Operating, Inc.,

Mr. Bradley guarantees payment of the plugging fee.

Operator's full Name: Four Way Operating, Incorporated,

Complete Address: Box #698, Great Bend, Kansas.

Lease Name: Schmeid Well No. A-2

Location: SE-NW-SE Sec. 21 Twp. 8 Rge. (E)(W) 25

County Graham Total Depth 3975 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bradley was instructed to plug the well as follows:

300'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3974'--4 1/2" Production casing cemented with 150 Sx. Well
plugged back to 3826'. Top perforations @ 3765'.

Push plug to 3700', set 10' rock bridge and 4 Sx. cement
with dump bailer. Pull 4 1/2" casing and squeeze well with
35 sacks gel using 5 sacks hulls in initial gel and follow
with 60 Sx. cement.

Very truly yours,

W. L. Mitchell
Conservation Division Agent