

State of Kansas



15-065-20237-00-02

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Popp of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Popp guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name: Babcock Well No. 1

Location: App.-SW-NE-SW Sec. 21 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3676' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Popp was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED

STATE CORPORATION COMMISSION

JUL 1 1969 Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

W. L. Nichols
Conservation Division Agent

7/1/69