



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 6 1973

CONSERVATION DIVISION  
Wichita, Kansas

11-6-73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sam Wagner of Red Tiger Drilling Company has this

date requested permission to plug the following described well:

Mr. Wagner guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Josaphine Well No. 1

Location: NE-NE-SW Sec. 23 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3920' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Wagner was instructed to plug the well as follows:

330'--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 340' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

*W. L. D. [Signature]*  
Conservation Division Agent