



15-065-20329-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1970  
CONSERVATION DIVISION  
Wichita, Kansas

5-19-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. John Crowe of Garvey Drilling Company, has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: Route #2, Great Bend, Kansas.

Lease Name: Richmeier Well No. E-1

Location: CNE-SE Sec. 27 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 4055' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

219'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 100 Sx. cement thru DP. Pull DP to 250' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent