

State of Kansas



15-065-20102-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION COMMISSION
DEC 7 1967
12-7-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name: St. John Well No. B-1

Location: NE-NE-SW Sec. 33 Twp. 8 Rge. (E)(W)25

County Graham Total Depth 3770 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

210'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1000' to 1175'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

M. L. Dickson

Conservation Division Agent