

State of Kansas



15-065-20203-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

2-12-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drlg. Co. Inc. has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated.

Complete Address: Box #797, Great Bend, Kansas.

Lease Name: Richmeier Well No. 1

Location: CNE-NE Sec. 35 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 4065' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx.  
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*M. L. Pickels*

Conservation Division Agent