

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 14 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Schamberger Well No. A-1 Tract #3, Well #1

Location: NE-NE-NE Sec. 36 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 4353' Oil Well

Gas Well  Input Well X SWD Well  D & A  Lost Hole

Mr. Unruh was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 140 Sx.  
3975'--5 1/2" casing cemented on bottom with 125 Sx. Well plugged back to  
4039'. Top of perforations @ 3925'.

Push plug to 3900', sand back to 3875' and set 5 Sx. cement with dump  
bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks  
gel and 150 Cu. Ft. cement, staged.

Very truly yours,

*M. L. Nichols*

Conservation Division Agent