

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

APR 14 1972

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of SouthWest Casing Pulling Co., has this  
date requested permission to plug the following described well:Mr. Clark guarantees payment of the plugging fee.Operator's full Name: Petroleum Management, Incorporated,Complete Address: Box #922, Great Bend, Kansas.Lease Name: Clark Well No. 1 Tract #5, Well #1Location: NE-NE-SE Sec. 36 Twp. 8 Rge. (E)(W) 25County: Graham Total Depth 4040' Oil Well Gas Well  Input Well X SWD Well  D & A  Lost Hole Mr. Clark was instructed to plug the well as follows:223'--8 5/8" Surface casing, cement circulated with 125 Sx.4039'--5 1/2" casing cemented on bottom with 75 Sx. Top of perforations @  
3830'.Sand well back to 3800' and set 5 Sx. cement with dump bailer. Pull  
5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150  
Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent