

15-065-02795-00-01

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of South West Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Bell Well No. 2 Tract #4, Well #2

Location: W/2-SE-NE Sec. 36 Twp. 8 Rge. (E)(W)25

County: Graham Total Depth 3935' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

240'--8 5/8" Surface casing, cement circulated with 150 Sx.
3928'--5 1/2" Production casing cemented on bottom with 75 Sx. Top perforations from 3908' to 3912'.

Sand well back to 3875' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent