



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

AUG 18 1964
8-18-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling Co. has this

date requested permission to plug the following described well:

Martin & Keller
 Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Martin & Keller,

Complete Address: 713 Kennedy Building, ^{Tulsa, Oklahoma} ~~Wichita,~~ Kansas.

Lease Name: Davis Well No. 1

Location: NW-NW-NW Sec. 1 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3975 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

212' 0-8 5/8" Surface pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

" " 190' with 1/4 sk hulls and 20 Sx. cement.

" " 40' with 1/2 sk hulls and 10 Sx. cement.

Very truly yours,

M. L. Nichols
 Conservation Division Agent