

State of Kansas



15-179-20045-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 1967  
10-16-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Duane Born of Paine Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Ben B. Tepper,

Complete Address: 7751 CARONDELET AVE. CLAYTON, MISSOURI 63105  
830 North Mission, Wichita, Kansas.

Lease Name: Niblock Well No. 2

Location: Appr. CS/2-SE-NW Sec. 2 Twp. 8 Rge. (E)(W) 26

County Sheridan Total Depth 4173 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Born was instructed to plug the well as follows:

220'--7"Od Surface pipe, cement circulated with 125 Sx. (6 1/4" hole)/  
Dakota section from 835' to 1000'.

Circulate hole with heavy mud. Pull DP to 1020' and displace 55 Sx.  
cement thru DP. Pull DP to 240' and displace 15 Sx. cement thru DP.  
Pull DP. Set bridge @ 40' with = sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

W. L. Dehler  
Conservation Division Agent