

15-179-20068-00-00

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1968
CONSERVATION DIVISION
Wichita, Kansas

12-24-68

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Paine Drilling, Incorporated,

Complete Address: Box "D", Hill City, Kansas.

Lease Name: Andregg Well No. 2

Location: NE-NW-SW Sec. 2 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3885 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

211'--7" OF Surface casing, cement circulated.
3871'--4 1/2" Production casing cemented on bottom with 75 Sx. Top of cement @ 3200' (Temp. Survey). Top of Dakota section @ 1015'.

Sand well back to 3850' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 20 sacks gel plus 5 sacks hulls and 100 Sx. cement staged.

Very truly yours,

Conservation Division Agent