

State of Kansas



15-179-20390-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 29 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
10-29-74

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Reiter of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Reiter guarantees payment of the plugging fee.

Operator's full Name: Ben F. Tepper,

Complete Address: 420 South Dixie, Coral Gables, Florida.

Lease Name: Niblock Well No. 3

Location: NE-SW-NW Sec. 2 Twp. 8 Rge. (E)(W) 26

County: Sheridan Total Depth 3865' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Reiter was instructed to plug the well as follows:

196'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. [Signature]  
Conservation Division Agent