

State of Kansas



15-179-20014-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1967

5-31-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ray Rice of Sterling Drilling Co., has this
date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Joe Katz Oil a/c, Benjamin B. Tepper, Agent,

Complete Address: 7751 Carondelet Ave., Clayton, Missouri.

Lease Name: Niblock Well No. A-2

Location: CSE_SE Sec. 3 Twp. 8 Rge. (E)(W) 26

County Sheridan Total Depth 3865 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

215'--7" OD Surface pipe, cement circulated with 150 Sx. (6 1/4" hole)

Circulate hole with heavy mud, set plug @ 540' and 15 Sx. cement.

"	"	215' with 1/4 sk. hulls & 15 Sx. cement.
"	"	40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

H. B. Nichols
Conservation Division Agent