

State of Kansas



15-179-20031-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1967  
7-31-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Inc., has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita Ave., Russell, Kansas.

Lease Name: Niblock Well No. 1

Location: CE/2-SE/<sup>NE</sup>~~SW~~ Sec. 3 Twp. 8 Rge. (E)(W) 26

County Sheridan Total Depth 3935' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

225' -- 8 5/8" Surface pipe, cement circulated with 140 Sx. Dakota section from 1500' to 1675'

Set plug thru DP from 1700' to 1400' with 100 Sx. cement.

Pull DP to 240' and displace plug thru DP to 180' with 20 Sx.

cement. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent