

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21871-0020

LEASE NAME Ostmeyer

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR H & C Oil Operating, Inc.

SEC. 15 TWP. 8S RGE. 25W (E) or (W)

ADDRESS P. O. Box 86 Plainville, KS 67663

COUNTY Graham

PHONE # (913) 434-7434 OPERATORS LICENSE NO. 8914

Date Well Completed

Character of Well Oil

Plugging Commenced 1-4-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-5-94

The plugging proposal was approved on (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3911'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	276'	none
				4 1/2	3872'	633'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom @ 3725' & dumped 4 sks cement. Shot @ 2242 & 2101, worked pipe. Spotted 40 sks cement @ 2100. Shot @ 1739, 1232 & 1013, worked pipe. Spotted 35 sks w/100# hulls @ 1150'. Shot @ 842 & 633, worked pipe. Spotted 35 sks w/100# hulls @ 633. Pulled to 275, circulated 40 sks w/100# hulls to surface. Pulled rest of pipe, topped off w/15 sks. 60/40 pos 10% gel. (If additional description is necessary, use BACK of this form.) Plugging complete.

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: H & C Oil Operating, Inc.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 13th day of January, 19 94

Irene Herzberg
Notary Public

My Commission Expires:



STATE OF KANSAS RECEIVED
JAN 18 1994
CORPORATION COMMISSION
Wichita, Kansas