

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 065-22,090-0000

LEASE NAME Ostmeyer

WELL NUMBER 3

SPOT LOCATION SE NE NW

SEC. 15 TWP. 8 RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 11-13-84

Plugging Commenced 11-13-84

Plugging Completed 11-13-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558, Garden City, KS 67846

PHONE (316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? Attached If not, is well log attached? Yes

Producing formation None Depth to top \_\_\_\_\_ bottom T.O. 3930

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	266	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged thru drill pipe with a total of 180 sks 50/50 PozMix, 6% gel, 3% CC as follows: 20 sks from 2100'-2008', 100 sks from 1250'-797', 40 sks from 300'-129', 10 sks from 40' to surface and 10 sks in rat hole. Cement was displaced with mud leaving mud between the plugs. Plugging was completed at 3:30 p.m. 11-13-84.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell License No. \_\_\_\_\_  
Address Hays, Kansas

STATE OF Kansas COUNTY OF Finney, ss.

Millard L. Lindsay (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Millard L. Lindsay  
(Address) P.O. Box 558, Garden City, K

SUBSCRIBED AND SWORN TO before me this 16 day of November, 1984

Betty J. Purdy  
Notary Public

My Commission expires: 6 Aug 1986

RECEIVED  
STATE CORPORATION COMMISSION  
11/20/84  
NOV 26 1984  
CONSERVATION DIVISION  
Wichita, Kansas

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: ..... November 19, 1984 .....  
month day year

API Number 15- 065-22,090-0000  
 East  
 West

OPERATOR: License # ... 5293 .....  
Name ..... Helmerich & Payne, Inc. ....  
Address ..... P.O. Box 558 .....  
City/State/Zip ... Garden City, KS 67846 .....  
Contact Person Millard L. Lindsay .....  
Phone ..... 316-276-3693 .....

SE. NE. NW Sec. 15. Twp. 8. S. Rge. 25. (location)  
4290 ..... Ft North from Southeast Corner of Section  
2970 ..... Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # ..... 5665 .....  
Name ..... Pioneer Drilling .....  
City/State ..... Plainville, KS 67663 .....

Nearest lease or unit boundary line ..... 2970 ..... feet.  
County ..... Graham .....  
Lease Name ..... Ostemeyer ..... Well# 3

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

If OWWO: old well info as follows:  
Operator .....  
Well Name .....  
Comp Date ..... Old Total Depth .....  
Projected Total Depth ..... 3900 ..... feet  
Projected Formation at TD ..... L-KC .....  
Expected Producing Formations ..... L-KC .....

Depth to Bottom of fresh water ..... 160 ..... feet  
Lowest usable water formation ..... Dakota .....  
Depth to Bottom of usable water ..... 1200 ..... feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set ..... 250 ..... feet  
Conductor pipe if any required ..... None ..... feet  
Ground surface elevation ..... 2376 ..... feet MSI.  
This Authorization Expires ..... 4-18-85 .....  
Approved By ..... 10-18-84 ..... *E*

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date ..... 10-17-84 ..... Signature of Operator or Agent *Millard Lindsay* Title Dist. Prod. Manager  
MHC/KDHE 10/18/84 Form C-1 4/84