

15-065-02791-0000

STATE OF KANSAS STATE CORPORATION COMMISSION


Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 211 No. Broadway Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 20 Twp. 8 Rge. (E) 25 (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE Lease Owner Tenneco Oil Company Lease Name Adelia Schmeid B Well No. 1 Office Address 2000 Classen Center, N. Bldg., Oklahoma City, Character of Well (completed as Oil, Gas or Dry Hole) oil Okla. Date well completed 19 Application for plugging filed March 15 19 66 Application for plugging approved 19 Plugging commenced March 20 19 66 Plugging completed March 24 19 66 Reason for abandonment of well or producing formation depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols Producing formation Depth to top Bottom Total Depth of Well 3886 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: 0, 202', 8 5/8", 202', none. Row 2: 0, 3886, 5 1/2", 3886, 1521.20

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 3815'. Dumped 20 gallons of sand and 3 gallons of rock. Mixed 5 sacks of cement and dumped at 3795'. Pulled pipe to 600'. Pumped in 20 sacks of Baroid gel and circulated. Pulled pipe to 540'. Mixed 20 sacks of cement and pumped into 5 1/2" casing. Pulled pipe to 196'. Mixed 20 sacks of cement and pumped into 5 1/2" casing. Pulled remaining pipe. Filled hole with mud to 35', set 10' rock bridge and capped hole with 10 sacks of cement.

RECEIVED STATE CORPORATION COMMISSION

APR 22 1966

CONSERVATION DIVISION Wichita, Kansas

4-22-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc. Address Box 486, Ellinwood, Kansas

STATE OF Kansas COUNTY OF Barton ss. Dean Wells

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells Ellinwood, Kansas


(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 66

(Signature) J. Rader

Notary Public.

My commission expires July 7, 1968



15-065-02791-0000

LOG

COMPANY: C. U. BAY  
 CONTRACTOR: EMPIRE DRILLING COMPANY  
 FARM: SCHMEID "B"-1  
 LOCATION: NE NE NE  
 SEC. 20-8S-25W  
 GRAHAM COUNTY, KANSAS  
 COMMENCED: 7-7-54  
 COMPLETED: 7-17-54

0	TO	218	SAND AND SHALE
218	TO	525	SHALE
525	TO	1375	SHALE AND SAND
1375	TO	1830	SHALE AND SHELLS
1830	TO	2073	SHALE
2073	TO	2110	ANHYDRITE
2110	TO	2175	SHALE
2175	TO	2605	SHALE AND SHELLS
2605	TO	2720	SHALE
2720	TO	2890	SHALE AND LIME
2890	TO	3015	SHALE AND SHELLS
3015	TO	3170	LIME
3170	TO	3270	SHALE AND LIME
3270	TO	3440	LIME
3440	TO	3520	SHALE AND LIME
3520	TO	3660	SHALE AND LIME
3660	TO	3705	LIME AND SHALE
3705	TO	3889	LIME
3889	T.D.		

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAY 16 1966  
 5-16-66

SET 202' OF 8-5/8" SURFACE CASING, CEMENTED WITH 125 SACKS OF CEMENT.  
 ELEVATION: 2369 D.F.  
 SET 3887' - 5 1/2" CASING + CEMENTED WITH 125 SACKS OF CEMENT.

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE SCHMEID "B"-1, NE NE NE OF SECTION 20, TOWNSHIP 8S, RANGE 25 WEST, GRAHAM COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

*Dan J. Kornfeld*  
 - DAN J. KORNFELD -

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 21st JULY 1954.

MY COMMISSION EXPIRES December 5, 1954.

*Ernie B. Garner*  
 NOTARY PUBLIC



**McADAMS PIPE & SUPPLY CO.**  
PIPE FOR EVERY PURPOSE

P. O. DRAWER 960  
BRISTOW, OKLAHOMA 74010

May 13, 1966

15-069-02791-00-00

RECEIVED  
STATE CORPORATION COMMISSION

MAY 16 1966

5-16-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

State of Kansas  
State Corporation Commission  
Conservation Division  
212 North Market  
Wichita, Kansas -67202

Gentlemen:

Attached is our check #45331 in the amount of \$38.86 for plugging assessment for the A. Schmeid #1, C NE NE, Section 20-8-25W, Graham County, Kansas. This well belonged to Tenneco Oil Company and was plugged in their name.

Also, as requested, enclosed is well log. Plugging record was forwarded to you by Pipe Pullers, Inc.

Yours very truly,

T. P. McAdams, Jr.,

TPMJr:mh

Encls.