


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-065-00808-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County County. Sec. 21 Twp. 8S Rge. 25W (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines SE SE SW

Lease Owner Burch Drilling Co., Inc.

Lease Name Schmeid Well No. 1

Office Address 1011 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-2-59 19

Application for plugging filed 1-8-59 19

Application for plugging approved 1-2-59 19

Plugging commenced 1-2-59 19

Plugging completed 1-2-59 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricus

Producing formation Depth to top Bottom Total Depth of Well 3981' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug set @ 600' w/20 sx. cement
2nd plug set @ 210' w/20 sx. cement
3rd plug set @ 40' w/10 sx. cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Burch Drilling Co., Inc.
Address 1011 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Earl M. Burch, (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl M Burch

(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January

July 27, 1960.



RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1959 Notary Public.

PLUGGING
FILE SEC 21 T 8 R 25W
BOOK PAGE 10 LINE 13

CONSERVATION DIVISION
Wichita, Kansas
1/12/59

15-065-00808-00-00

WELL LOG

Burch Drilling Co., Inc.
1 SCHMEID
SE SE SW 21-8S-25W
Graham County, Kansas

Set 8 5/8" @ 221' w/165 sx.
COMM: 12-19-58
COMP: 1-2-59
ELEVATION: 2459 KB

D & A

2185 Shale & Shells
2220 Anhydrite
2350 Shale & lime streaks
3665 Lime & Shale
3842 Lime
3890 Lime & Shale
3981 Lime

3981 Rotary Total Depth

TOPS
HEEBNER 3711
TORONTO 3735
LANSING 3752
BASE KANSAS CITY 3973

DST # 1 3775-3794 Open 1/2 hr. Rec. 50' very slightly oil specked mud. IBHP (30min) 0, IFP & FFP 0, FBHP 510#.

DST # 2 3810-3824 Open 1 hr. Rec. 15' mud. IBHP (30min) 0, IFP & FFP 0, FBHP (30min.) 70#.

DST # 3 3824-3838 Open 1 hr. Rec. 38' slightly oil specked mud. IBHP (30 min) 420#, IFP & FFP 0, FBHP (30min) 125#.

DST # 4 3872-3910 Open 1 hr. Rec. 22' mud. IBHP (30min) 0#, IFP & FFP 0, FBHP(30min) 790#.

DST # 5 3912-3955 Open 45 min. Rec. 26' oil specked mud. All pressures were 0.

STATE OF KANSAS, COUNTY OF SEDGWICK:

I, Earl M. Burch, President of Burch Drilling Co., Inc. being duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Earl M. Burch

Subscribed and sworn to before me this 8th day of January 1959.

Gina Harrison
Notary Public

My commission expires: July 27, 1960.



PLUGGING
FILE SEC 21 T 8 R2SW
BOOK PAGE 10 LINE 13

1/12/59
RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1959
CONSERVATION DIVISION
Wichita, Kansas