


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-065-02857-0000  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines Graham County. Sec. 21 Twp. 8 Rge. 25 (E) W (W)  
Lease Owner Great Bend Pipe & Supply Co., Inc.  
Lease Name Schmied "D" Well No. 1  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 5-28-62 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 5-30-62 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well ELDON PETTY  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3917 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262'	None
				4-1/2"	3916'	1112'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Checked hole to 3917', ran 20' of sand and~~  
dumped 4 sacks of cement @ 3897' with dump  
bailer. Pulled 4 1/2" casing to 550', circulated  
with gel mud and pumped in 20 sacks of cement.  
Pulled 4 1/2" casing to 170' and pumped in 20  
sacks of cement. Pulled balance of 4 1/2" casing,  
set rock bridge and ~~ran~~ ran 10 sacks of cement  
to base of cellar.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 5 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (~~owner~~) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 19 62

My commission expires May 20, 1964

Milton J. Volin Notary Public.

INVOICED

DATE 6/6/62  
INV. NO. 5104-w

COMPANY: C. U. AY  
 Denver, Colorado

Rotary Drilling Commenced: 4-26-52  
 Rotary Drilling Completed: 5-6-52

LOCATION: SECTION "D" #1  
 SW SW 1/4 Section 21-83-25W  
 Graham County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY  
 Wichita, Kansas

CASING RECORD: 262' 8 5/8" 2 1/2" casing set at 262' in a 1 1/2" hole, cemented with 160 sacks cement.  
 3916' (115 jts.) 4 1/2" O.D. 9 1/2" casing set at 3916' in a 7 7/8" hole, cemented with 125 sacks cement.

LOG

Figures indicate bottom formation - measurements from top rotary bushing.)

Clay	40
Shale	235
Sand	240
Shale	440
Shale & Shells	548
Anhydrite	570
Shale, Shells & Breccia of Pyrite	925
Coal	1225
Shale & Sand	1960
Shale	2100
Anhydrite	2192
Shale	2200
Shale & Shells	2450
Shale	2890
Lime	3065
Shale	3200
Lime & Shale	3415
Lime & Shale & Breccia of Sand	3475
Lime	3595
Lime & Shale	3670
Lime	3850
Lime & Shale	3906
Shale	3717 Rotary T.D.

Circulate for samples at	3710'
" " " "	3715'
" " " "	3754'
" " " "	3888'
" " " "	3906'
" " " "	3917'

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAY 3 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

5/3/62

Slope test at 2000' - 0° off.  
 Slope test at 3000' - 0° off.  
 SLM at 3000' - O.K.  
 Slope test at 3717' - 0° off.  
 SLM at 3717' - O.K.

The undersigned, C. W. Sebeto, Attorney-in-fact of PICKRELL DRILLING COMPANY, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.


PICKRELL DRILLING COMPANY  
 By [Signature]  
 Attorney-in-fact

COUNTY OF KANSAS )  
 )  
 COUNTY OF DEBOWICK )

On this 19th day of May, 1952, before me the undersigned, a Notary Public in and for the County and State aforesaid personally appeared C. W. Dobito, to me known to be the identical person who subscribed the name of Pickrell Drilling Company to the foregoing instrument as its Attorney-in-fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein

Given under my hand and seal of office the day and year last above

[Signature]  
 Notary Public



My Commission expires January 28, 1953.