

15-065-21632-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Graham SEC. 21 TWP. 8S RGE. 25W XXX  
 Location as in quarters or footage from lines:

SENESE


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Industrial Gas Services, Inc.  
 Lease Name Babcock Well No. 1-21  
 Office Address 4501 Wadsworth Blvd., Wheat Ridge, CO 80033  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed 6-10-82  
 Application for plugging filed 4-18-85  
 Plugging commenced 6-3-85  
 Plugging completed 6-3-85  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Well had reached economic limit  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation Lansing/K.C. Depth to top 3714 bottom 3932 T.D. 4000  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	240'	-0-
				4-1/2"	3999'	-0-
				Note: D.V. Tool set at 1020' with 200 Sx's cement.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Down 4-1/2" casing at 200# maximum pressure. 25 Sx's of 60/40 POZ. 10% Gel and 3% C.C. with 1 Sx of hull spaced with 16 Sx's of gel and 1 Sx of hull. Released wiper plug and pumped 100 Sx's of 60/40 POZ. 10% Gel, 3% C.C. and 1 Sx of hull. Came back and capped well the next day with 20 Sx's of 60/40 POZ, 10% Gel, 3% C.C. The casing was cut 3' below the ground level, and covered with dirt.

RECEIVED  
 STATE CORPORATION COMMISSION

6/12/85  
 JUN 12 1985

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Poe Well Services

CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF COLORADO COUNTY OF JEFFERSON, ss.  
HENRICK SARKISSIAN (employee of ~~owner~~ or ~~owner~~ or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God. INDUSTRIAL GAS SERVICES, INC.

(Signature) Muriel Sarkissian (ENG.)  
 4501 Wadsworth Blvd.  
 (Address)  
 Wheat Ridge, CO 80033

SUBSCRIBED AND SWORN TO before me this 10<sup>TH</sup> day of June, 1985

L. Diane McLean  
 Notary Public.

L. Diane McLean  
 4501 Wadsworth Blvd.  
 Wheat Ridge, CO 80033

My Commission expires: Feb 21, 1986



