

API NUMBER 065-22682 0500
 LEASE NAME Babcock
 WELL NUMBER 1
 SPOT LOCATION C-NE-NW
 SEC. 21 TWP. 8 RGE. 25 (E) or (W)
 COUNTY Graham
 Date Well Completed 10-22-92
 Plugging Commenced 10-22-92
 Plugging Completed 10-22-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Helberg Oil Company

ADDRESS Box 32 Morland, KS 67650

PHONE # (913)-627-5665 OPERATORS LICENSE NO. 5669

Character of Well D&A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation LKC Depth to top 3632 bottom 3860 T.D. 3860

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	200	8 5/8"	200	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug set at 2070' with 25 sacks cement 60/40 Poz 6% Gel; 2nd Plug set at 1150' with 100 sacks cement and 1 sack flo-seal 60/40 Poz 6% Gel; 3rd Plug set at 240' with 40 sacks cement 60/40 Poz 6% Gel; 4th Plug set at 40' with 10 sacks cement 60/40 Poz 6% G d; 15 sacks in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Services License No. _____
 Address Hays, KS 67601

STATE OF Kansas COUNTY OF Graham, ss.

Jerry M. Helberg (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Helberg

(Address) Box 32 Morland, KS 67650

NOTARY PUBLIC- State of Kansas
FAYE E. MINIUM
 My Appt. Exp. _____

My Commission expires: 10-13-94

SUBSCRIBED AND SWORN TO before me this 26 day of October, 1992
Faye E. Minium
 Notary Public OCT 27 1992

10/27/92
 CONSERVATION DIVISION
 WICHITA, KANSAS
 Revised 01-84