

15-069-00712-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 22 Twp. 8S Rge. 25 (E) W (W)

Location as "NE/CNW'SW" or footage from lines SW SW SE

Lease Owner Peel-Hardman Oil and Gas Producers

Lease Name B. St. John Well No. 1

Office Address P.O. Box 359, Hoisington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 4 1955

Application for plugging filed June 4 1955

Application for plugging approved June 4 1955

Plugging commenced June 4 1955

Plugging completed June 4 1955

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3960 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	160'	8 5/8"	160'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 3960' to 156 1/2' - heavy rotary mud
 156 1/2' to 155' - wooden plug
 155' to 109' - 15 sacks cement
 109' to 41 1/2' - heavy rotary mud
 41 1/2' to 40' - wooden plug
 40' to 6' - 10 sacks cement & 1/2 sack hulls
 6' to surface- cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn W. Peel

Address P.O. Box 359, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Glenn W. Peel (employee of owner) or ~~(owner)~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN W. PEEL


(Signature) BY: Manuel Herbert

P.O. Box 359, Hoisington, Kansas

(Address) June 8th 1955

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1955

My commission expires June 4, 1959



Manuel Herbert
Notary Public
JUN 5 - 1955
CONSERVATION DIVISION
Wichita, Kansas
6-9-55

PLUGGING
FILE SEC 22 T 8 R 25W
BOOK PAGE 124 LINE 29

DRILLERS' LOG

Company: Peel-Hardman Oil and Gas Producers

SW SW SE

Farm Name: B. St. John Well No. 1

Sec. 22, Twp. 8S, Rge. 25W,

Total Depth: 3960'

County : Graham,
Kansas

Comm: 5-26-55 Comp: 6-4-55

Contractor: Glenn W. Peel

Elevation:

Casing: 8 5/8" 160' cem.

Production: Dry

Figures below indicate bottoms of formations:

Clay and sand	0 -	160
Shale and shells		2130
Anhydrite		2162
Shale and shells		2255
Shale and brown lime		2500
Shale and shells		2855
Shale		3005
Shale and lime streaks		3110
Lime and shale		3300
Shale and lime streaks		3500
Shale and lime		3585
Lime		3960
Total Depth		3960

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: Way Herbes

SUBSCRIBED AND SWORN to before me this 8th day of June, 1955.

My commission expires: June 4, 1959

Marian M. Herbel
Notary Public



PLUGGING
RMA SEC 22 T 8 R 25W
BOOK PAGE 124 LINE 29