

15-065-30180-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Graham County. Sec. 22 Twp. 8 Rge. 25 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines NE NE SW  
Lease Owner Don E. Pratt Oil Operations  
Lease Name Babcock Well No. 1  
Office Address P.O. Box # 370 Hays, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed 10-3-1966  
Application for plugging filed 10-3-1966  
Application for plugging approved 10-3-1966  
Plugging commenced 10-3-1966  
Plugging completed 10-3-1966  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	203'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled rotary hole to a depth of 450' where 1st plug was set using 20 sacks & 1 1/2 sks Hulls.  
Filling hole with rotary mud to a depth of 210' where 2nd plug was set using 20 sks cement.  
Rotary mud was used to fill hole to a depth of 40' where 3rd plug was set using 10 sks.  
cement and filling hole to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 6 1966  
CONSERVATION DIVISION  
Wichita, Kansas  
10-6-66


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.  
Address Route # 2 Victoria, Kansas

STATE OF KANSAS, COUNTY OF ELLIS, ss.  
Leo F. Dreiling (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
LEO F. DREILING VICTORIA, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of October, 19 66



Elmer Weltz  
Elmer Weltz Notary Public.

My commission expires October 26, 1968

15-065-30180-00-00

L. J. DREILING and SONS, Inc.  
VICTORIA, KANSAS

WELL LOG

Company Don E. Pratt Oil Operations  
Hays, Kansas  
Farm Babcock No. 1

Sec. 22 Twp. 8 Rng. 25  
Location NE NE SW

Total Depth 3900'

County Graham  
2354 K.B.

Comm. 9-26-66 Comp. 10-3-66

Elevation: 2351 D. F.

Contractor L. J. Dreiling & Sons, Inc.  
Victoria, Kansas

2349 G. R.

Casing Record

Cement Record

Production:

203' 8-5/8"

150 sacks

D & A

OCT 6 1966  
10-6-66  
REGISTRATION DIVISION  
VICTORIA, KANSAS

Figures Indicate Bottom of Formations

0'	40'	Sand
40'	203'	Shale
203'	800'	Shale
800'	1650'	Shale
1650'	1800'	Sand
1800'	1842'	Sand
1842'	2079'	Shale & Red Bed
2079'	2112'	Anhy.
2112'	2295'	Shale & Shells
2295'	2580'	Shale & Shells
2580'	2833'	Shale & Lime
2833'	2995'	Shale & Lime
2995'	3117'	Shale & Lime
3117'	3260'	Shale & Lime
3260'	3420'	Shale & Lime
3420'	3520'	Shale & Lime
3520'	3652'	Lime & Shale
3652'	3709'	Lime
3709'	3725'	Lime
3725'	3763'	Lime
3763'	3825'	Lime
3825'	3870'	Lime
3870'	3872'	Lime
3872'	3900'	Lime

STATE OF KANSAS)  
                                  )ss  
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Babcock # 1.

*Leo F. Dreiling*  
LEO F. DREILING

Subscribed and sworn to before me this 4th day of October 1966.

*Elmer Welty*  
NOTARY PUBLIC

My commission expires: October 26, 1968

