


15-065-00469-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 23 Twp. 8S Rge. 25W (E) (W)
Location as "NE/CNW/SE" or footage from lines SE SE SE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Minium "C" Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 5 1958
Application for plugging filed October 5 1958
Application for plugging approved October 5 1958
Plugging commenced October 5 1958
Plugging completed October 5 1958
Reason for abandonment of well or producing formation No commercial quantities of oil found.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3940 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	233'	233'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set No. 1 Plug at 550' with 25 sacks cement. Set No. 2 Plug at 230' with 15 sacks cement. Set No. 3 Plug at 40' with 10 sacks cement.


RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1958
CONSERVATION DIVISION
Wichita, Kansas

1029-58

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of Imperial Oil of Kansas, Inc.) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.
(Signature) By: Raymond L. Bacon V-P.
780 Fourth National Building, Wichita 2, Kansas
(Address)



Subscribed and Sworn to before me this 23rd day of October, 1958
My commission expires July 7, 1962
Mona L. Latier
Mona L. Latier Notary Public.

PLUGGING
FILE SEC 23T 8 R 25W
BOOK PAGE 139 LINE 17

15-069-00469-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Minium "C" No. 1
SE SE SE Sec. 23-8S-25W
Graham County, Kansas

Total Depth: 3940'

Elevation: 2382' RB
Production: D & A

Commenced: 9-25-58 Completed: 10-5-58

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 233' with 160 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Surface Sand & Shale	235'	Anhydrite	2105' (/ 277)
Sand & Shale	700'	Heebner	3667' (-1285)
Hard Sand & Shale	1240'	Toronto	3691' (-1309)
Hard Shells & Shale	1395'	Lansing	3708' (-1326)
Dakota Sand	1485'	Rotary Total Depth	3940' (-1558)
Shells & Shale	2105'		
Anhydrite	2138'		
Shale & Red Bed	2360'		
Shale & Lime	3700'		
Lime	3940'		
Total Depth	3940'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

PLUGG 3
 FILE SEC. 23 T. 8 R. 25W
 BOOK PAGE 139 LI F 17

By: Ray L. Bacon
Vice President

Subscribed and sworn to before me this 21st day of October, 1958.

My Commission Expires:

RECEIVED
STATE CORPORATION COMMISSION

July 17, 1962

OCT 29 1958

Mona L. Latier
Notary Public

CONSERVATION DIVISION
Wichita, Kansas

10-29-58