

15-005-20626-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Graham County, Sec. 23 Twp. 8S Rge. 25W (E) (W) X  
Location as "NE/CNW%SW%" or footage from lines NE NE SW  
Lease Owner Okmar Oil Company  
Lease Name Josaphine Well No. No. 1  
Office Address 1130 Vickers-KSB&T Building, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed November 2 19 73  
Application for plugging filed November 2 19 73  
Application for plugging approved November 2 19 73  
Plugging commenced November 2 19 73  
Plugging completed November 2 19 73  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Nichols  
Producing formation Depth to top Bottom Total Depth of Well 3920 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	330'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 @ 1,125' w/110 sx  
Plug #2 @ 340' w/30 sx  
Plug #3 @ 40' w/10 sx - 50-50 pozmix, 6% gel.


RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling Company  
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss.  
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens  
1720 Wichita Plaza, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 1973



My commission expires May 24, 1977  
Linda C. Mowrey Notary Public.

DRILLERS LOG

No. 1 Josaphine

CASING RECORD:  
8-5/8" @ 330'  
w/185 sx cement

COMPANY: Okmar Oil Company  
CONTRACTOR: Red Tiger Drilling Co.  
COMMENCED: October 25, 1973  
COMPLETED: November 2, 1973

DESCRIPTION:  
NE NE SW  
23-8S-25W  
Graham County,  
Kansas

TOTAL DEPTH: 3,920'

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	960	
Shale w/Sand Stringers	960	1685	
Shale	1685	1690	
Sand	1690	1875	
Shale	1875	2093	
Anhydrite	2093	2143	
Shale	2143	2735	
Shale & Lime	2735	2955	
Lime	2955	3490	
Shale & Lime	3490	3587	
Lime	3587	3920	

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
11-15-73

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens  
Linda H. Dickens

Subscribed and sworn to before me this 8th day of November, 1973.

Linda C. Mowrey  
Notary Public

My Commission Expires:  
May 24, 1977

