

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR R.A. Comeau

API NO. 15-065-21,527 00-00

ADDRESS 308 West Mill
Plainville, Kansas 67663

COUNTY Graham

FIELD Schmeid Northeast

**CONTACT PERSON Charles G. Comeau

PROD. FORMATION Kansas City

PHONE 913-434-4686

LEASE Waltz

PURCHASER Mobil Oil Corporation

WELL NO. #5

ADDRESS Box 900
Dallas, Texas 75221

WELL LOCATION NE NE SW

2310 Ft. from South Line and

2310 Ft. from West Line of


the SW/4 SEC. 10 TWP. 8s RGE. 25W

DRILLING Pioneer Drilling Company

CONTRACTOR ADDRESS 308 West Mill

Plainville, Ks 67663

PLUGGING CONTRACTOR ADDRESS



WELL PLAT

KCC
KGS
MISC
(Office Use)

TOTAL DEPTH 3970' PBDT

SPUD DATE 11-25-81 DATE COMPLETED 12-11-81

ELEV: GR 2374' DF 2377' KB 2379'

DRILLED WITH (~~CAMER~~) (ROTARY) (~~KAMR~~) TOOLS (New) / (~~USED~~) casing.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface casing	12 1/4"	8 5/8"	24#	238.59'	common	150	3%cc 2%gel
Production	7 7/8"	4 1/2"	10.5#	3943.06'	ASC	125	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4 per ft.		3841-44

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8	3918.75	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gallon 15% Mud Acid & 2 gallon Inhibitor	3841-44

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1981 12/30/81

Date of first production 12-11-81 Producing method (flowing, pumping, gas lift, etc.) Pumping unit Gravity

RATE OF PRODUCTION PER 24 HOURS Oil 15 bbls. Gas 1 MCF Water 2 % bbls. CFPB

Disposition of gas (vented, used on lease or sold) Perforations

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum _____ DEPTH 120'

Estimated height of cement behind Surface Pipe _____

DV USED? None

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
sand and shale	0'	248'		
shale and sand	248'	1200'		
sand and shale	1200'	1865'		
sand and shale	1865'	2073'		
anhydrite	2073'	2110'		
anhydrite	2110'	2115'		
shale and shells	2115'	2120'		
shells and shale	2120'	2568'		
shale	2568'	2830'		
lime and shale	2830'	2870'		
lime and shale	2870'	3100'		
lime and shale	3100'	3250'		
lime and shale	3250'	3370'		
lime and shale	3370'	3485'	topeka	3410
lime and shale	3485'	3640'		
lime and shale	3640'	3738'	heebner	3648
lime and shale	3738'	3819'	toronto	3673
lime and shale	3819'	3885'	lansing	3692
lime and shale	3885'	3970'	base	3905
lime and shale	3970'	R.T.D.		

AFFIDAVIT

STATE OF KANSAS, COUNTY OF ROOKS SS,

Charles G. Comeau OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Secretary-Treasurer (FOR)(OF) LIBERTY ENTERPRISES, INC.


OPERATOR OF THE Watts LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 5 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 11th DAY OF December, 1981, AND THAT


ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) 
Charles G. Comeau

SUBSCRIBED AND SWORN BEFORE ME THIS 29th DAY OF December 1981

SHARON GARVERT
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Expires 10/24/84


NOTARY PUBLIC
Sharon Garvert

MY COMMISSION EXPIRES: