

KANSAS

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-068-20458-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas
6-21-71

Operator's Full Name Petroleum, Incorporated,
Complete Address 300 West Douglas, Wichita, Kansas.
Lease Name Richmeier Well No. E-1
Location App: CS/2-S/2-NW Sec. 35 Twp. 8 Rge. (E) (W) 25
County Graham Total Depth 4030'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Garvey Drilling Company,
Address 300 West Douglas, Wichita, Kans. License No.
Operation Completed: Hour 7:30 PM Day 18 Month 6 Year 1971

The above well was plugged as follows:

219'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru
DP from 1250' to 925'. Pulled DP, to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 6/22/71
INV. NO. 3879-W