

Jo
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

15-065-30359-00-00

APR 5 1966
4-5-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Richmeier Well No. B-2

Location SW-SW-NE Sec. 35 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3990

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 11:30AM Day 2 Month 4 Year 1966

The Above well was plugged as follows:

115'--8 5/8" Surface pipe, cement circulated with 60 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 120', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sk. hulls

and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Finkel*
Well Plugging Supervisor

INVOICED
DATE 4/5/66
INV. NO. 2994-W