

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,
 Complete Address Box #922, Great Bend, Kansas.
 Lease Name Schamberger Well No. Tract #3, Well #1
A-1
 Location NE-NE-NE Sec. 36 Twp. 8 Rge. (E) (W) 25
 County Graham Total Depth 4353'
 Abandoned Oil Well Gas Well Input Well X SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor SouthWest Casing Pulling Company, Incorporated,
 Address Box #364, Great Bend, Kansas. License No. 399
 Operation Completed: Hour 5:15 PM Day 8 Month 4 Year 1972

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 140 Sx.
3975'--5 1/2" casing cemented on bottom with 125 Sx. Well plugged back to 4039'. Top of perforations @ 3925'.
Pushed plug to 3900', sanded back to 3875' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing (1215') and squeezed well initially with 5 sacks hulls and 10 sacks
and followed with 110 Cu. Ft. cement from 1225' to 900' then 16 sacks gel from 900'
to 260' and followed with 30 Cu. Ft. cement from 260' to 185' then 4 sacks gel from
185' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-
in pressure-150#. Final shut-in pressure-75#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickel
Well Plugging Supervisor

INVOICED

DATE 4/17/72
INV. NO. 5563-W