

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

APR 14 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address Box #922, Great Bend, Kansas.

Lease Name Clark Well No. 1 Tract #5, Well #1

Location NE-NE-SE Sec. 36 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 4040'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor South West Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:00 PM Day 11 Month 4 Year 1972

The above well was plugged as follows:

223'--8 5/8" Surface casing, cement circulated with 125 Sx.

4039'--5 1/2" casing cemented on bottom with 75 Sx. Top of perforations @ 3830'.

Sanded well back to 3800' and set 5Sx. cement with dump bailer. Pulled 5 1/2" casing

(1231') and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed

with 110 Cu. Ft. cement from 1225' to 900' then 16 sacks gel from 900' to 260' and

followed with 30 Cu. Ft. cement from 260' to 185' then 4 sacks gel from 185' to 25'

and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure

-150#. Final shut-in pressure-50#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Pichler
Well Plugging Supervisor

INVOICED

DATE 4/17/72

INV. NO. 5565-W