

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1974
12-10-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thornton E. Anderson

Complete Address 340 R.H. Garvey Bldg., 300 W. Douglas, Wichita, Kansas 67202

Lease Name Minium "B" Well No. 2

Location SE SW SW Sec. 36 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 4051'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, ~~Ellinwood~~ Ellinwood, Kansas License No. 462

Operation Completed: Hour 10:20 A Day 9 Month 12 Year 1974

The above well was plugged as follows:

- Total Depth 4051' 8 5/8 csg set at 164' cwc 100 sk.
- 4 1/2 csg set at 4050' cw 125 sk. & perf. (3830')
- Set 4 1/2 wood plug at 3800' -poured 20' sd -dumped 4 sk cem W/dump bailer. (3800-3750)
- Cutoff & recovered 1408' of 4 1/2 csg.
- Pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs hulls-70 sk 50-50 poz 6%-
- 15 sk gel & water -released 8 5/8 plug & pumped 50 sk 50-50 poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo R. Massey
Well Plugging Supervisor

DATE 12/10/74
INV. NO. 425-W