

15-065-02794-00-01

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address Box #922, Great Bend, Kansas.

Lease Name Bell Well No. 1

Location SE-SE-NE Sec. 36 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3980'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:15 PM Day 8 Month 4 Year 1972

The above well was plugged as follows:

243'--8 5/8" Surface casing, cement circulated with 150 Sx.
3980'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to
3865'. Top perforations from 3791' to 3795'.

Sanded well back to 3775' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(600') and squeegeed well initially with 5 sacks hulls and 10 sacks gel and followed
with 110 Cu. Ft. cement from 1225' to 900' then 16 sacks gel from 900' to 260' and
followed with 30 Cu. Ft. cement from 260' to 185' then 4 sacks gel from 185' to 25'
and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-
200#. Final shut-in pressure-100#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 4/17/72
INV. NO. 5564-W