

KANSAS

Jep
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,
Complete Address Box #922, Great Bend, Kansas.
Lease Name Bell Well No. 2 Tract #4, Well #2
Location W/2-SE-NE Sec. 36 Twp. 8 Rge. (E) (W) 25
County Graham Total Depth 3935'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 5:30 PM Day 11 Month 4 Year 1972

The above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 150 Sx.
3928'--5 1/2" Production casing cemented on bottom with 75 Sx. Top perforations from 3908' to 3912'.
Sanded well back to 3875' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed with 110 Cu. Ft. cement from 1225' to 900' then 16 sacks gel from 900' to 260' and followed with 30 Cu. Ft. cement from 260' to 185' then 4 sacks gel from 185' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure--150#.
Final shut-in pressure--75#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. S. Daniels*
Well Plugging Supervisor

DATE 4/17/72
INV. NO. 5566-W