

KANSAS

2

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address Box #922, Great Bend, Kansas.

Lease Name Schamberger Well No. Tract #3, Well #2
A-2

Location CS/2-NE-NE Sec. 36 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3945'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 2:30 PM Day 8 Month 4 Year 1972

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 175 Sx.

3936'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to

3928'. Top of perforations @ 3921'.

Sanded well back to 3900' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing

and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed with 110

Cu. Ft. cement from 1225' to 900' then 16 sacks gel from 900' to 260' and followed

with 30 Cu. Ft. cement from 260' to 185' then 4 sacks gel from 185' to 25' and finally

10 Cu. Ft. cement from 25' to bottom of cellar. Maximum- pump-in pressure--200#.

Final shut-in pressure-100#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dichek
Well Plugging Supervisor

DATE 4/17/72
INV. NO. 5561-W